BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Improvements to roads and drains at Badrappa Layout and surrounding area in Ward no. 08 Kodigehalli.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	125.82	Removing & Refixing stone slabs of drains and pointing in C.M.(1:3)	Cum	80.56	Rupees Eighty and Fifty Six Paise Only
2	461.34	KSRB 2-2.2:Earthwork excavation for foundtion of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary Soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	Cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
3	76.89	KSRB 4-1.3:Providing and layingi n position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications.	Cum	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only
4	146.79	KSRB 4.2.2:Providing andlaying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates @ 0.459 cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed - 2008, machine mixed, concrete laid in layres not exceeding 15 cms, thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase,lintles, retaining walls, return walls, walls (any thickness) includng attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills fillets etc, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	6491.88	Rupees Six Thousand Four Hundred Ninety One and Eighty Eight Paise Only
5	7.34	KSRB 4.9-1:Providing T.M.T Steel reinforcement for RCC Work including straightening, cutting, bending hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wasstge shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	64243.42	Rupees Sixty Four Thousand Two Hundred Forty Three and Forty Two Paise Only
6	1118.40	KSRB 4-6.4:Providing and removing centering, shuttering, strutting proppoing etc, and removal of formwork for Vertical surface such as walls at any thickness including attached pilasters butresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	310.58	Rupees Three Hundred Ten and Fifty Eight Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	293.58	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 10cms thick	Sqm	825.74	Rupees Eight Hundred Twenty Five and Seventy Four Paise Only
8	2328.00	Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded	Nos	37.10	Rupees Thirty Seven and Ten Paise Only
9	1000.00	5.29(b) Providing and fixing Pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with toop and bottom wideth 114 and 165 mm respectively 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, includng form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unoading lead and lift transportatin etc, complete.	Nos	331.78	Rupees Three Hundred Thirty One and Seventy Eight Paise Only
10	180.00	KSRRB 15-19.1:Providing and applying ready mix priming coat over concrete/ masonry/asbestos cement sheet/ plastered surfaces including preparing the surface after thoroughly cleaning of oil grease, dirt and other foreign matter, and sand preparing including cost of materials, labour complete as per specifications.	Sqm	27.56	Rupees Twenty Seven and Fifty Six Paise Only
11	180.00	KSRRB 15-20.1:Providing and applying floor painting with redy mix paint in two coats (excluding priming coat) on new concret / asbestos cement sheet / plastered surfaces brushing to give an even shade qafter preparing the surface after throughly cleaning oil, diert, dust other foreign matter and sand preparing including cost of materials, labour, complete as per specifications.	Sqm	53.00	Rupees Fifty Three Only
12	461.34	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	106.00	Rupees One Hundred Six Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.